



## Addendum #02

Date: 11/17/2021

Project Name: Illinois Sports Facilities Authority

HVAC/AHU Renovation Phase XI – Guaranteed Rate Field – Chicago, IL

Project Number:21276

This narrative addresses RFI questions based on items represented in the original contract documents.

### Revisions

1. Drawing M1.04, note #5 indicates to install a new VAV RTU, although this RTU is not scheduled.
  - a. A schedule for RTU-1 has been added and is on Drawing M4.01 in the Addendum #01 set posted on 11/15/2021.
2. Drawing M1.06, note #13 indicates a CU-3 to serve a cooling unit on the level above on M1.08. Schedule for CU-3 is incomplete, and the associated cooling coil unit is unclear.
  - a. The “CONDENSING UNIT SCHEDULE” has been completed and provided on Drawing M4.01 in the Addendum #01 set posted on 11/15/2021.
  - b. CU-3 serves indoor DX fan coil unit AC-7. The “DX FAN COIL UNIT SCHEDULE” has been completed and provided on Drawing M4.01 in the Addendum #01 set posted on 11/15/2021.
3. Equipment utilizing chilled water will require disconnection and reconnection of chilled water services. Who will be responsible for draining and filling of these systems?
  - a. The mechanical contractor will be responsible for isolating the equipment, draining and refilling the chilled water system. Chilled water contains glycol. Assume 30% PG and confirm with building engineer prior to filling.
4. Drawing M1.06, detail #6 indicates exhaust fan EF-104 for Section 105 Ice Cream that is not scheduled.
  - a. EF-104 has been added to the Exhaust Fan Schedule and is on Drawing M4.01 in the Addendum #01 set posted on 11/15/2021
5. Drawing M1.08, detail #3 indicates exhaust fan EF-4C-01 for Storage 4.22 that is not scheduled.
  - a. EF-4C-1 is not scheduled in the addendum. The information for that fan is attached.
6. Drawing M3.03, details #3, #4, and #5 are blank.
  - a. These are the details for the AHUs. They’ve been addressed in the Addendum #01 set posted on 11/15/2021.

END OF RESPONSES



|    |      |              |              |           |          |        |        |     |      |
|----|------|--------------|--------------|-----------|----------|--------|--------|-----|------|
| EF | 4C-1 | STORAGE 4.22 | STORAGE 4.22 | GREENHECK | SQ-100-A | INLINE | DIRECT | N/A | 1000 |
|----|------|--------------|--------------|-----------|----------|--------|--------|-----|------|

**NOTES:**

1. FACTORY MOUNTED AND WIRED DISCONNECT SWITCH.
2. PROVIDE 14" HIGH PREFABRICATED, INSULATED, ROOF CURB WITH COUNTERFLASHING CURB CAP.
3. ALUMINIMUM BIRD SCREEN.
4. MOTORIZED BACKDRAFT DAMPER SHIPPED LOOSE TO BE INSTALLED BY MC AND WIRED BY EC. PROVIDE TRANSFORMER AS REQUIRED.
5. MOTOR COVER/BELT GUARD.
6. PROVIDE 1 SPARE SET OF BELTS FOR OWNER'S ATTIC STOCK.
7. VIRBRATION ISOLATION KIT FURNISHED LOOSE BY MANUFACTURER TO BE INSTALLED BY MC.
8. NEMA PREMIUM EFFICIENCY MOTOR WITH SHAFT GROUNDING RING.
9. ECM FAN WITH SINGLE 0-10V CONTROLLER FACTORY MOUNTED ON FAN.
10. FAN SHALL BE CONTROLLED BY SPACE TEMPERATURE SENSOR/THERMOSTAT FURNISHED AND WIRED BY BASC.
11. FAN SHALL BE CONTROLLED BY TIME CLOCK, FURNISHED AND INSTALLED BY EC.
12. ACCEPTABLE ALTERNATE MANUFACTURERS: COOK, TWIN CITY.

|     |       |      |      |      |      |     |    |   |             |
|-----|-------|------|------|------|------|-----|----|---|-------------|
| 0.7 | 1,725 | 10.2 | 0.24 | 1725 | 0.25 | 120 | 60 | 1 | 1,7,8,10,12 |
|-----|-------|------|------|------|------|-----|----|---|-------------|