



September 23, 2022

## **ISFA GUARANTEED RATE FIELD – HVAC FY2023**

### **ADDENDUM #1**

#### **1.0 DRAWINGS**

1. Sheet MD1.1, View 3: Mechanical Partial Demo. Plan – Service Corridor Sec. 8
  - a. Corrected error. Drawings revised to show the correct condensing unit to remain.
2. Sheet MD1.2, View 1: Mechanical Partial Demo. Plan – 200 Level Sec. 3
  - a. Revised chilled water piping demolition scope to include all piping in mechanical room. Demolish and replace existing isolation valves. Drain system as necessary.
3. Sheet M1.1, View 3: Mechanical Partial Demo. Plan – Service Corridor Sec. 8
  - a. Corrected error. Drawings revised to show the correct condensing unit to remain. Revised to show correct location of CU-02.
4. Sheet M1.2, View 1: Mechanical Partial New Plan – 200 Level Sec. 3
  - a. Revised chilled water piping new work scope to include all piping in mechanical room. Demolish and replace existing isolation valves. Refill system as necessary.
5. Sheet ED1.1, View 3: Electrical Partial New Plan – Service Corridor Sec. 8
  - a. Corrected error. Drawings revised to show the correct condensing unit to be demolished.
6. Sheet E1.1, View 4: Electrical Partial New Plan – Service Corridor Sec. 8
  - a. Corrected error. Drawings revised to show correct location of CU-02.

#### **2.0 CLARIFICATIONS**

1. For fan coil replacement scope (FCU-1 and FCU-2), intent is to replace all chilled water piping up to the mains. Main location to be verified in field. Existing isolation valves to be replaced with new. Drain and re-fill upstream system as necessary.