



Date: November 22, 2024  
Project Name: GRF Waste/Vent Piping FY25  
Project Number: 24310  
Addendum No.: 1

This Addendum consists of additions and/or modifications to the plans and/or specifications to the contract documents. The changes to these documents are only in the manner and to the extent stated herein. All drawings have “Issued for Addendum No. 1” and “11.22.2024” in the title block. Changes are bubbled and tagged with revision Delta 1. This Addendum supersedes any oral or written information previously delivered.

### Revisions

1. P01.100, P01.200, P01.300, and P01.400 are updated:
  - a. To clarify existing conditions for additional horizontal branches to additional drains connected to the ramp vertical storm stack.
  - b. Drain, stack, and horizontal pipe runs are diagrammatically shown to aid the bidder.
  - c. Additional keyed notes are included to aid the bidder.
  - d. Photos on the drawings from the field are included to aid the bidder.
  - e. The entire sheet is considered updated by bubbling the sheet number on the sheet. Review these sheets entirely.
  
2. PD03.S03, P03.S03, PD03.103, P03.103, PD03.203, P03.203, PD03.303, P03.303, PD03.403, P03.403, PD03.503, and P03.503 are updated:
  - a. To clarify existing conditions.
  - b. To clarify the scope mentioned during the bid walk through which was not yet shown on the drawings.
  - c. To epoxy line an additional floor drain at Level 100 floor (related to pipe replaced at Service Level ceiling space below).
  - d. To replace p-trap with acid resistant pipe and fittings for lined drain of item c above.
  - e. To clarify both sanitary and kitchen waste piping are to be replaced with Orion/Watts Blueline FRPP acid resistant piping.
  - f. To clarify the point of demolition and new work scope at Level 500 as mentioned in bid walk through; photos are provided.
  - g. The entire sheet is considered updated by bubbling the sheet number on the sheet. Review these sheets entirely.
  
3. P07.203 and P07.204 are updated:
  - a. To clarify existing conditions for two floor receptor locations which require additional scope to make access to epoxy line the receptor body and downstream pipe.
  - b. The portions bubbled on the sheet are updated.



1. PD03.S03, P03.S03, PD03.103, P03.103, PD03.203, P03.203, PD03.303, P03.303, PD03.403, P03.403, PD03.503, P03.503, P07.203, and P207.04.

END OF ADDENDUM